HIGH TEMPERATURE APPLICATIONS OF STRUCTURAL CERAMICS QUARTERLY PROGRESS REPORT July - September 1981 Samuel J. Schneider Project Manager Center for Materials Science National Bureau of Standards U. S. Department of Commerce

Washington, D. C. 20234

PREPARED FOR THE UNITED STATES DEPARTMENT OF ENERGY

Under Contract No. DE-A105-800R20679

"This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights."



TABLE OF CONTENTS

		PAGE
INTRODUCTIO	N	. 1
Subtask A.	High Temperature Fracture of Structural Ceramics	2
Subtask B.	Crack Growth Mechanism Maps	3
Subtask C.	Microstructure and Phase Alteration	5
Subtask D.	Microstructure and Fracture in Reactive Environments	19

DESCRIPTION OF TAXABLE

1000

The state of the s

SHEELS A. High Tomparature Tructure of Authorital Cornelles. . 1

Statement Co. Microsophysics and These Statements and Manager as

Suffered D. Minterstrature and Processes In Associa-

NBS-5.2.10 - HIGH TEMPERATURE APPLICATIONS OF STRUCTURAL CERAMICS

E. R. Fuller, R. J. Fields, T. J. Chuang, A. Dragoo and S. J. Schneider

> National Bureau of Standards Center for Materials Science Washington, D. C. 20234

INTRODUCTION

The achievement of higher efficiency thermochemical engines and heat recovery systems requires the availability of high temperature, high performance structural materials. Structural ceramics such as SiC, Si₃N₄ and certain Al₂O₃-Si₃N₄ combinations have received particular attention for these applications due to their basic characteristics of good strengths coupled with good corrosion and thermal shock resistances. Even with these positive attributes, improved reliabilities and extended lifetimes under service conditions are necessary for structural ceramics to gain industrial acceptance and use. The problems are mechanical and/or chemical in nature and are enhanced by the fact that these materials are subjected to high temperatures, reactive environments and extreme thermal gradients.

With an objective of improved performance for heat engine/heat recovery applications the NBS program on structural ceramics addresses these problems through the determination of the critical factors which influence mechanical and microstructural behavior. The activities of the program are grouped under four major subtasks with each designed to develop key data, associated test methods and companion predictive models. The status of the subtasks are detailed in the following sections.

DESCRIPTION OF THE PARTY OF THE

T. F. Poller, S. J. Stelde, T. J. Chang, A. Traggo and S. L. Manueldar

National Sereous of Campings Colors to the Particular Polymer Co. 19814

INTRO STATE

The exclusive appears require the southernies of high requests and the best recovery and the state of the southern and the best recovery and the state of the sta

The production and objective of represent perference for leavest ordered the section of the sect

NBS 5.2.10(A) - HIGH TEMPERATURE FRACTURE OF STRUCTURAL CERAMICS

RESULTS FROM PRIOR QUARTERS

Four-point bend tests on notched bars of SisAlON, were completed and the results compared with previous work on an yttria-doped SiC (NCX34) and with literature values for Si_3N_4 . Reduced scale testing rigs using SiC were manufactured to test small billets of experimental materials. Fifteen different compositions of Si₃N₁ + Y.A.G. materials obtained from Professor Tien of University of Michigan using these rigs were tested at 1300 °C in order to avoid oxidation. Further studies of Tien's Si_3N_4 were conducted to ascertain critical stress intensity factors and to clarify some inconsistencies in earlier results. A literature survey of available data on fracture toughness, crack growth behavior and creep properties of SiC, Si3N, and sialon was completed. Four-point bending tests under constant displacement rate were performed on several SiC and sialon specimens. For $\alpha\text{-SiC}$ tested in air, the results showed little oxidation and high resistance to slow crack growth up to 1300 °C. For sialon specimens ($Si_{6-z}^{A1} {}_{2}^{0} {}_{2}^{N} {}_{8-z}$), it was found that as z increases, the susceptibility to crack growth and oxidation decreases.

The asymptotic behavior of the stress intensity factor as a function of crack length for 4-point bending at small and large crack lengths was investigated in more detail. This work is useful for future numerical solution schemes. Also, an analysis of load-deflection curves which compute crack growth behavior (V-K) without requiring a knowledge of Young's modulus or machine compliance was completed.

High temperature four-point bending tests under constant displacement rate condition have been performed on <u>notched</u> reaction sintered SiC specimens. Several ways of initiating cracks were tried before a chevron notch was utilized. This produced a stable crack growth period and a sharp crack.

A paper entitled "Slow Crack Growth in Sialon" was presented at the International Symposium on Fracture Mechanics of Ceramics, University Park, Pennsylvania July 17, 1981. A paper entitled "Effects of Deformation on the Fracture Behavior of $\mathrm{Si_3N_4}$ and $\mathrm{Sialons}$ " was presented at the 2nd NATO

PARTY AND ADDRESS OF THE PARTY OF THE PARTY

SECURIOR STEELS STORY OF PERSONS

The results compared with previous week so an approximation of the results and sing tention of the results and results

of case longs for a posts builting as small and large cases tongston and
of cases longs for a posts builting as small and large cases tongston and
laverationed in more detects. This work in contact for comme constitute
the column of the contact of the contact of the contact tongston as browned and
longs of the column of the contact of the contact tongston as browned and
longs of the column of the contact of the contact of the contact of the contact of the column of the colu

-iner til besente pulleren factore an independent of the puller of the p

Descriptions of tracture to extend to extend the continue of t

Advanced Study Institute held at Falmer, England from the 27th of July to the 7th of August, 1981. Both of these papers presented work which came partly from this task.

DISCUSSION OF CURRENT ACTIVITIES

Further analyses of the four-point bend test were completed. One analysis allows the determination of the tensile creep behavior from flexural testing of trapezoidal cross-sections. A further analysis deducing tensile behavior from bending and compression tests will be finished shortly. These results will be written up and published. A sensitivity analysis just performed on four-point bending allows us to judge what type of crack growth behavior we may be able to measure properly in flexure. Materials not having these crack growth characteristics require a mechanically more stable test specimen such as the double-torsion specimen. This has proved to be the case for $\alpha\textsc{-SiC}$ and we are now fabricating these sorts of specimens from this material. We are still awaiting the delivery of $\beta\textsc{-SiC}$ to complete work on this material. In the meanwhile, we are working ahead on the properties of the siliconized silicon carbide.

NBS 5.2.10(B) - CRACK GROWTH MECHANISM MAPS

RESULTS FROM PRIOR QUARTERS

Preliminary maps for $\mathrm{Si}_3\mathrm{N}_4$ have been drawn. A computer program for automatically drawing maps from K-V data has been written. Data for SiC has been collected with the aim of constructing a crack growth mechanism map. An evaluation of K_{IC} was made because its definition by ASTM E-399 conflicts with common usage in the ceramic community. A preliminary crack growth mechanism map for a commercial hot pressed SiC was constructed from published information. The literature survey of fracture and crack growth mechanisms was completed for SiC, $\mathrm{Si}_3\mathrm{N}_4$ and sialon.

new place from homeone where went to deal of the party of

DESCRIPTION OF COLUMN ASSISTANCE

restricts allow the intermentation of the county trees belowing them analysis allows the intermentation of the county trees belowing them the intermentation of the county of the trees belowing the state of the county of the co

AND RESIDENCE AND PARTY AN

DESTRUCTION NAMED ADDRESS OF TAXABLE

The state of the s

A crack growth model based on diffusion mechanisms was developed. The model entails a grain-boundary crack growing in steady state due to applied stress by stress assisted surface and grain-boundary diffusion. By further assuming the grain on either side of the crack behaves elastically, the model predicts a unique K-V relationship and a threshold K below which no crack growth will take place. A comparison of this prediction to a set of creep crack growth data on sialon at 1400 °C showed good agreement.

The paper entitled "A diffusive crack growth model for creep fracture" (NBSIR 81-2255) was accepted for publication in J. Am. Ceram. Soc.

An investigation into the energy release rate of this crack growth model was included in this paper. The results show that J is the total amount of energy consumption rate which consists of a portion consumed in the creation of new crack surfaces and the remaining portion dissipated in the matter transport processes.

The theoretical prediction of V-K functional relationship based on diffusion-controlled crack growth was mapped into K-T space in order for the future data to fit in the diffusive crack growth area of the mechanism maps.

A paper entitled, "Crack Growth Mechanism Maps" was published in Advances in Fracture Research. This paper describes the concept of crack growth mechanism maps and details their construction.

DISCUSSION OF CURRENT ACTIVITIES

Data obtained in part A above is being analyzed here in order to construct a crack growth mechanism map for NCX34. Since this material (i.e., Y_2O_3 doped silicon carbide) is one of the most promising nitrogen ceramics, the map may prove very useful.

Due to the work performed in this DoE sponsored research project, the investigators were invited to participate in a recent NATO Advanced Study Institute on nitrogen ceramics. Also, we have been invited to present our work on time dependent failure mechanisms in silicon carbide to next summer's Gordon Conference on ceramics. Much of the work to be presented directly emanates from this DoE project. Our main emphasis in the review



and evaluation of crack growth theories has been in diffusive crack growth theories. We believe that this is the long term mechanism of failure and, hence, the one of technological importance.

NBS-5.2.10(C) - MICROSTRUCTURE AND PHASE ALTERATION

RESULTS FROM PRIOR QUARTERS

X-ray analyses were performed on various sialon and as-received silicon carbide samples. Also, preliminary x-ray data were obtained on alpha silicon carbide oxidized in the temperature range from 1200 to 1500 °C.

A literature survey was begun to collect references on the oxidation and the high-temperature thermal and mechanical properties of silicon carbide.

A concept for a high-temperature x-ray furnace was developed in which the sample serves as the heating element.

DISCUSSION OF CURRENT ACTIVITIES

Phase Analysis

The various SiC polytypes, including β -SiC, can be indexed on hexagonal unit cells which differ principally in the stacking in the c-axis direction. In considering the structural polytypes of SiC, it is convenient to focus on the placement of Si-atoms, since the C-tetrahedra can be referenced with respect to the Si-sublattice. The Si-atoms can assume either a cubic packing or a hexagonal packing in the c-axis direction. The SiC polytypes are a consequence of various combinations of these two types of packing [1].

In view of the number of potential structures, it appears advisable to use a structural analysis procedure which takes account of these structural variations in a fundamental manner. Such a procedure is one that assigns occupation probabilities to each lattice site in the (001) planes above the first two fiducial planes for which the site occupations are



defined, a priori. This procedure recognizes that the x-rays inherently average over many unit cells so that occupation probabilities are consistent with the method of measurement. The resulting theoretically calculated structure factors and predicted diffraction pattern will have diffraction maxima which correspond to the range of structural polytypes, but each maxima will have a weight, or composite probability, assigned to it. Among peaks characteristic of a given polytype, relationships between the composite probabilities are to be expected. Comparison of observed peaks and peak intensities with the predicted pattern will establish the set of polytypes which are consistent with the data and will indicate those peaks which are assignable to impurities. It is also expected that this analysis can be employed in oxidation studies to target groups of peaks for observation during the oxidation process. Such an approach may identify those polytypes which are most subject to oxidation.

Theoretical calculation of the structural factors and predicted x-ray diffraction pattern are now in progress.

Structural Ceramics Bibliography

A structural ceramics bibliography is attached. Although SiC and oxidation studies were emphasized in the literature search, references also were collected for ${\rm Si_3N_4}$ and ${\rm Si_3N_4}$ -oxide systems and for other properties.

High-Temperature X-ray Diffraction

Designs for a high-temperature x-ray diffraction furnace were prepared. These include drawings for the furnace housing (cover and endplate) and the ceramic insulation.

Oxidation Studies

SiC sample holders and setter plates were prepared and conditioned at 1500 °C. Currently, two furnaces for this study are being relocated to another laboratory, and work on this study is suspended until suitable




electrical power is installed.


1. Parthe', Erwin, Crystal Chemistry of Tetrahedral Structures, NY, Gordon and Breach, 1964.

STRUCTURAL CERAMICS BIBLIOGRAPHY


- A. Oxidation and Other Reactions
- [1] Bremen, W., Naoumidid, A.; nickel, H.
 Oxidationsverhalten des pyrolytisch abgeschieden b-SiC
 unter einen atomsphaere aus CO-CO2-gasgemischen. J.
 Nucl. Mater. 71: 56-64; 1977. CA 88:12080684F.
- [2] Schlichting, Juergen; Kriegesmann, Jochen.
 Oxidationsverhalten von heissgepresstem Siliciumcarbid.
 Ber. Dt. Keram. Ges. 56(3-4): 72-75; 1979. CA
 91:06043522T.
- [3] Costello, J. A.; Tressler, R. E. Oxidation kinetics of hot-pressed and sintered a-SiC. J. Am. Ceram. Soc. 64(6): 327-331; 1981.
- [4] Heuer, A. H.; Ogbuji, L. U., Mitchell, T. E. The microstructure of oxide scales on oxidized Si and SiC single crystals. J. Am. Ceram. Soc. 63(5-6): 354-355; 1980.
- [5] Costello, J. A.; Tressler, R. E.; Tsong, I. S. T. Boron redistribution in sintered a-SiC during thermal oxidation. J. Am. Ceram. Soc. 64(6): 332-335; 1981.
- [6] Smith, C. L. SiC-fission product reactions in HTGR TRISO UC2 and UCxOy fissile fuel: I, Kinetics of reactions in thermal gradient. J. Am. Ceram. Soc. 62(11-12): 600-606; 1979.
- [7] Smith, C. L. SiC-fission product reactions in HTGR TRISO UC2 and UCxOy fissile Fuel: II, Reactions under isothermal conditions. J. Am. Ceram. Soc. 62(11-12): 607-613; 1979.
- [8] McDonough, W. J.; Wu, C. Cm.; Morgan, P. E. D. Internal phase changes in dense Si3N4 associated with high-temperature oxidation. J. Am. Ceram. Soc., Comm. 64(3): C45-C47; 1981.
- [9] Hirai, Toshio; Niihara, Koichi; Goto, Takshi. Oxidation of CVD Si3N4 at 1550 deg to 1650 deg C. J. Am. Ceram. Soc. 63(7-8): 419-423; 1980.



- [10] Lewis, M. H.; Barnard, P. Oxidation mechanisms in Si-Al-O-N ceramics. J. Mater. Sci. 15: 443-448; 1980.
- [11] Lange, F. F. Phase relations in the system Si3N4-Si02-MgO and their interrelation with strength and oxidation. J. Am. Ceram. Soc. 61(1-2): 53-56; 1978.
- [12] Land, P. L.; Wimmer, J. M.; Burns, R. W.; Choudhury, N. S. Compounds and properties of the system Si-Al-O-N. J. Am. Ceram. Soc. 61(1-2): 56-60; 1978.
- [13] Lange, F. F.; Davis, B. I. Development of surface stresses during the oxidation of several Si3N4/CeO2 materials. J. Am. Ceram. Soc. 62(11-12): 629-631; 1979.
- [14] Guzman, I. Ya.; Litvin, Yu. N.; Gerasimov, V. I.; Ochagova, I. G. Oxidation of ceramics based on silicon carbide with nitride and oxynitride binders at high temperatures in various oxygen-containing gaseous media. Issled. Nitridov., 3rd Mater. Vses. Nauchn. Semin. Metodam Poluch., Svoistvam Obl. Primen. Nitridov, 1973. Kiev: Akad. Nauk Ukr. SSR, Inst. Probl. Materialoved.; 124-129; 1975. CA 87:12089340C.
- [15] Hinze, J. W.; Tripp, W. C.; Graham, H. C. The high-temperature oxidation of hot-pressed silicon carbide. Mater. Sci. Res. 9: 409-419; 1975. CA 86:26195750A.
- [16] Pasechnik, Yu. A.; Getsko, O. M.; Bantser, S. G.; Snitko, O. V. Luminescence of a silicon carbide surface during anodic oxidation. Opt. Spektrosk. 43(2): 372-374; 1977. CA 87:18143593C.
- [17] Keys, Lewis H. The oxidation of silicon carbide. Proc. Electrochem. Soc. 77-1 (Proc. Symp. Prop. High Temp. Alloys, 1976): 681-696; 1976. CA 89:08063732Y.
- [18] Rzechula, Jerzy; Pielak, Anna. Effect of feldspar fluxes on the oxidation of silicon carbide at 1273-1622 K. Szklo Ceram. 29(3): 68-70; 1976. CA 89:08063732Y.
- [19] Pampuch, R.; Jonas, S. New aspects of the oxidation of silicon carbide. Sci. Ceram. 9: 300-307; 1977. CA 90:04028078P.
- [20] Sanders, William A.; Johnston, James R. High velocity burner rig oxidation and thermal fatique behavior of silicon nitride and silicon carbide base ceramics to 1370 deg C. NASA Tech. Memo. NASA-TM-79040, E-9842. Cleveland: Lewis Res. Cent., NASA; 1978; 44 pp. CA 91:06043550A.:




- [21] Hayakawa, Junshiro; Isshiki, tokuichiro. Oxidation resistance of oxide bonded silicon carbide refractories. Part 1. Taikabutsu. 259: 394-400; 1979. CA 91:26215512H.
- [22] Lauche, J.; Tairov, Yu. M.; Tsvetkov, V. F.; Szczepanski, F. Study of the kinetics of oxidation of silicon carbide single crystals. Izv. Akad. Nauk SSSR, Neorg. Mater. 17(2): 254-257; 1981. CA 94:16128135F.
- [23] Krivoshein, D. A.; Maurakh, M. A.; Dergunova, V. S.; Petrov, Yu. N.; Lebedev, Yu. N.; Artem'eva, S. P. Mechanism of forming protective glassy films on the surface of the system zirconium diboride-zirconium carbide-silicon carbide-carbon during its oxidation. Poroshk. Metall., Kiev. 8: 58-62; 1980. CA 94:12088954P.
- [24] Grinshpunt, A. G.; Kashkul, V. V.; Anelok, L. I. Study of high-temperature transformations in electrode materials. Metallurgiya i Koksokhimiya. 69: 78-80; 1980. CA 93:22209106D.
- [25] Pampuch, R.; Ptak, W.; Jonas, S.; Stooch, J. Formation of ternary silicon-oxygen-carbon phase(s) during oxidation of silicon carbide. Mater. Sci. Monogr. 6(Energy Ceram.): 435-448; 1980. CA 93:18172469W.
- [26] Bantser, S. G.; Getsko, O. M.; Pasechnik, Yu. A.; Snitko, O. V. Electroluminescence of different silicon carbide polytypes in anodic oxidation. Ukr. Fiz. Zh. 25(1): 41-48; 1980. CA 92:14119048M.
- [27] Schlichting, Juegen. Silicon carbide as an oxidation-resistant refractory material. I. Oxidation and high-temperature corrosion behavior. Ber. Dtsch. Keram. Ges. 56(8): 196-200; 1979. CA 92:04027217N.
- [28] Schlichting, Juegen. Silicon carbide as an oxidation-resistant refractory material. II. Oxidation and high-temperature corrosion behavior. Ber. Dtsch. Keram. Ges. 56(9): 256-261; 1979. CA 92:08063327G.
- [29] Knoch, H.; Gazza, G. E. Effect of carbon impurity on the thermal degradation of an Si3N4-Y2O3 ceramic. J. Am. Ceram. Soc. 62(11-12): 634-635; 1979.




B. Strength


- [1] Seshadri, S. G.; Srinivasan, M. Estimation of fracture toughness by intrinsic flaw fractography for sintered alpha silicon carbide. J. Am. Ceram. Soc., Comm. 64(4): C69-C71; 1981.
- [2] Quinn, G. D.; Katz, R. N. Time-dependent high-temperature strength of sintered a-SiC. J. Am. Ceram. Soc. 63(1-2): 117-119; 1980.
- [3] McHenry, K. D.; Tressler, R. E. Fracture toughness and high-temperature slow crack growth in SiC. J. Am. Ceram. Soc. 63(3-4): 152-156; 1980.
- [4] Lankford, James. Uniaxial compressive damage in a-SiC at low homologous temperatures. J. Am. Ceram. Soc. 62(5-6): 310-312; 1979.
- [5] Rice, R. W.; Pohanka, R. C.; McDonough, W. J. Effect of stresses from thermal expansion anisotropy, phase transformations, and second phases on the strength of ceramics. J. Am. Ceram. Soc. 63(11-12): 703-710; 1980.
- [6] Bilby, B. A. Tewksbury lecture: putting fracture to work. J. J. Mater. Sci. 15: 535-556; 1980.
- [7] Karunaratne, B. S. B.; Lewis, M. H. High-temperature fracture and diffusional deformation mechanisms in Si-Al-O-N ceramics. J. Mater. Sci. 15: 449-462; 1980.
- [8] Lange, F. F.; Davis, B. I.; Clarke, D. R. Compressive creep of Si3N4/MgO alloys--Part 1 Effect of composition. J. Mater. Sci. 15: 601-610; 1980.
- [9] Lange, F. F.; Clarke, D. R.; Davis, B. I. Compressive creep of Si3N4/MgO alloys--Part 2 Source of viscoelastic effect. J. Mater. Sci. 15: 611-615; 1980.
- [10] Lange, F. F.; Davis, B. I.; Clarke, D. R. Compressive creep of Si3N4/MgO alloys--Part 3 Effects of oxidation induced compositional change. J. Mater. Sci. 15: 616-618; 1980.
- [11] Lange, F. F. Compressive surface stresses developed in ceramics by oxidation-induced phase changes. J. Am. Ceram. Soc. 63(1-2): 38-40; 1980.




- C. Phases, Polytypes and Microstructures
- [1] Parthe', Erwin. Crystal Chemistry of Tetrahedral Structures. New York: Gordon and Breach; 1964. Book.
- [2] Smith, David J.; Jepps, N. W.; Page, T. F.
 Observations of silicon carbide by high resolution
 transmission electron microscopy. J. Microsc. 114(1):
 1-18; 1978. CA 90:02014813N.
- [3] Jepps, N. W.; Page, T. F. Electron microscopy of interfaces between transforming polytypes in silicon carbide. J. Microsc. 116(1): 159-171; 1978. CA 91:16127823E.
- [4] Vodakov, Yu. A.; Mokhov, E. N.; Roenkov, A. D.; Saidbekov, D. T. Effect of crystallographic orientation on the polytype stabilization and transformation of silicon carbide. Phys. Stat. Solidi. A51(1): 209-215; 1979.
- [5] Jepps, N. W.; Page, T. F. 9R-HREM observations of a new silicon carbide polytype. J. Am. Ceram. Soc. 63(1-2): 102-103; 1980. CA 92:20167965E.
- [6] Heuer, A. H.; Fryburg, G. A.; Ogbuji, L. U.; Mitchell, T. E.; Shinozaki, S. b-.a transformation in polycrystalline SiC: I, Microstructural aspects. J. Am. Ceram. Soc. 61(9-10): 408-412; 1978. CA 89:22184609X.
- [7] Mitchell, T. E.; Ogbuji, L. U.; Heuer, A. H. b-.a transformation in polycrystalline SiC: II, Interfacial energies. J. Am. Ceram. Soc. 61(9-10): 412-413; 1978. CA 89:24202847E.
- [8] Ogbuji, L. U.; Mitchell, T. E.; Heuer, A. H. The b-.a transformation in polycrystalline SiC: III, The thickening of a plates. J. Am. Ceram. Soc. 64(2): 91-99; 1981. CA 94:20165839J.
- [9] Ogbuji, L. U.; Mitchell, T. E.; Heuer, A. H.; Shinozaki, S. The b-.a transformation in polycrystalline SiC: IV, A comparison of conventionally sintered, hot-pressed, reaction-sintered, and chemically vapor-deposited samples. J. Am. Ceram. Soc. 64(2): 100-105; 1981. CA 93:04030735F.
- [10] Shinozaki, Samuel S.; Sato, Hiroshi. Microstructure of SiC prepared by chemical vapor deposition. J. Am. Ceram. Soc. 61(9-10): 425-429; 1978.




- [11] Clarke, David R. High-resolution techniques and application to nonoxide ceramics. J. Am. Ceram. Soc. 62(5-6): 236-246; 1979.
- [12] Schneider, G.; Gauckler, L. J.; Petzow, G.; Zangvil, A. Phase equilibria in the system A14C3-Be2C-SiC. J. Am. Ceram. Soc. 62(11-12): 574-576; 1979.
- [13] Robertson, Wayne M. Thermal etching and grain-boundary grooving of silicon ceramics. J. Am. Ceram. Soc. 64(1): 9-13; 1981.
- [14] Greskovich, C. Microstructural observations on hot-pressed Si3N4. J. Am. Ceram. Soc., Comm. 64(2): C31; 1981.
- [15] Krivanek, O. L.; Shaw, T. M.; Thomas, G. The microstructure and distribution of impurities in hot-pressed and sintered silicon nitrides. J. Am. Ceram. Soc. 62(11-12): 585-590; 1979.
- [16] Lou, L. K. V.; Mitchell, T. E.; Heuer, A. H. Discussion of "Grain Phases in a Hot-Pressed MgO Fluxed Silicon Nitride." J. Am. Ceram. Soc. 61(9-10): 462-463; 1978.
- [17] Morgan, P. E. D. The a/b-Si3N4 question. J. Mater. Sci. 15: 791-793 (1980).
- [18] Lewis, M. H.; Bhatti, A. R.; Lumby, R. J.; North, B. The microstructure of sintered Si-Al-O-N ceramics. J. Mater. Sci. 15: 103-113; 1980.
- [19] Clarke, D. R. Microstructure of a 12H Mg-Si-A1-O-N Polytype alloy: intergranular phases and compositional variations. J. Am. Ceram. Soc. 63(3-4): 208-214; 1980.
- [20] Zangvil, A.; Gauchkler, L. J.; Ruehle, M. Indexed x-ray diffraction data for the sialon X-phase. J. Mater. Sci. 15: 788-790; 1980.
- [21] Lewis, M. H.; Bhatti, A. R.; Lumby, R. J.; North, B. Crystallization of Mg-containing phases in b'-Si-Al-O-N ceramics. J. Mater. Sci. 15: 438-442; 1980.
- [22] Land, P. L.; Wimmer, J. M.; Burns, R. W.; Choudhury, N. S. Compounds and properties of the system Si-Al-O-N. J. Am. Ceram. Soc. 61(1-2): 56-60; 1978.




- [23] Gauckler, L. J.; Weiss, J.; Tien, T. Y.; Petzow, G. Insolubility of Mg in b-Si3N4 in the system Al-Mg-Si-O-N. J. Am. Ceram. Soc. 61(9-10): 397-398; 1978.
- [24] Lou, L. K.; Mitchell, T. E.; Heuer, A. H. Impurity phases in hot-pressed Si3N4. J. Am. Ceram. Soc. 61(9-10): 392-396; 1978.
- [25] Naik, I. K.; Tien, T. Y. Subsolildus phase relations in part of the system Si,Al,Y/N,O. J. Am. Ceram. Soc. 62(11-12): 642-643; 1979.
- [26] Mitomo, M.; Yajima, Y.; Kuramoto, N. Thermal decomposition of Si-Al-O-N ceramics. J. Am. Ceram. Soc. 62(5-6): 316-317; 1979.
- [27] Weiss, J.; Gauckler, L. J.; Tien, T. Y. The system Si3N4-Si02-ZrN-Zr02. J. Am. Ceram. Soc. 62(11-12): 632-634; 1979.
- [28] Trigg, M. B.; McCartney, E. R. Reactions in the system Si-Ti-O-N. J. Am. Ceram. Soc. 63(1-2): 103-104; 1980.
- [29] Shinozaki, S.; Kinsman, K. R. Influence of structure on morphology in polycrystalline silicon carbide. Ceram. Microstruct., Proc. Int. Mater. Symp., 6th, 1976. Ed. by Fulrath, Richard M.; Pask, Joseph A. Boulder: Westview Press; 1977; pp. 60-70. CA 88:12077911X.
- [30] Clarke, D. R. Morphology of the transformation interface in reaction-sintered silicon carbide. J. Am. Ceram. Soc. 60(11-12): 539-540; 1977. CA 88:12077891R.
- [31] Tairov, Yu. M.; Tsvetkov, V. F.; Chernov, M. A.; Taranets, V. A. Investigation of phase transformations and polytype stability of beta-silicon carbide. Phys. Status Solidi A. 43(1): 363-369; 1977. CA 87:22175793J.
- [32] Kinsman, K. R.; Shinozaki, S. An uncommon mode of morphological development among coherent phases (silicon carbide). Scr. Metall. 12(6): 517-523; 1978. CA 89:18151332Y.
- [33] Dubey, Madan; Singh, G. Use of lattice imaging in the electron microscope in the structure determination of the 126R polytype of silicon carbide. Acta Crystallogr. A34(1): 116-120; 1978. CA 88:12082192T.




- [34] Heuer, A. H.; Lou, V.; Ogbuji, L.; Mitchell, T. E. Lattice resolution studies of engineering ceramics: silicon carbide and silicon nitride. J. Microsc. Spectrosc. Electron. 2(5): 475-480; 1977. CA 88:10065087V.
- [35] Shinozaki, Samuel S.; Noakes, John E.; Sato, Hiroshi. Recrystallization and phase transformation in reaction-sintered silicon carbide. J. Am. Ceram. Soc. 61(5-6): 237-242; 1978. CA 89:02010821V.
- [36] Safaraliev, G. K.; Tairov, Yu. M.; Tsvetkov, V. F. Thermodynamic analysis of solubility and transformation coefficient of boron in silicon carbide. Svoistva Legirovan. Poluprovodnikov. pp. 53-58; 1977. CA 88:26198570U.
- [37] Pandey, Dhananjai; Lele, S.; Krishna, P. Mechanism of the 2H -. 6H solid state transformation in silicon carbide. J. Cryst. Growth. 42: 644-650; 1977. CA 88:24180565M.
- [38] Vodakov, Yu. A.; Mokhov, E. N.; Roenkov, A. D.; Saidbekov, D. T. Effect of crystallographic orientation on the polytype stabilization and transformation of silicon carbide. Phys. Status Solidi. A51(1): 209-215; 1979. CA 90:18144403Q.
- [39] Ogbuji, L. U.; Mitchell, T. E.; Heuer, A. H.; Shinozaki, S. Discussion of "Microstructural characterization of 'REFEL' (reaction-bonded) silicon carbides." J. Mater. Sci. 14(9): 2267-2271; 1979. CA 91:22180126F.
- [40] Jepps, N. W.; Page, T. F. Intermediate transformation structures in silicon carbide. J. Microsc. 119(1): 177-188; 1980. CA 93:16159319C.
- [41] Pandey, Dhananjai; Lele, Shrikant; Krishna, P. X-ray diffraction from one-dimensionally disordered 2H crystals undergoing solid state transformation to the 6H structure. III. Comparison with experimental observations on silicon carbide. Proc. R. Soc., London. A369(1739): 463-477; 1980. CA 92:16138904D.
- [42] Lubrovskii, G. b. Natural superlattices in crystals. Probl. Fiz. Tekhnol. Shirokozonnykh Poluprovodn., Vses. Soveshch. Shirokozonnym Poluprovodn., 2nd, 1979. Leningrad: Akad. Nauk SSSR, Fiz.-Tekh. Inst.; 1980; pp. 150-164. CA 94:04020741M.



- [43] Inomata, Yoshizo; Uemura, Yohichiroh; Inoue, Zenzaburo; Tanaka, Hidehiko. Energy stored in a grain boundary formed by rotation along a hexagonal lattice plane in silicon carbide crystals. Yogyo Kyokaishi. 88(10): 628-633; 1980. CA 93:22213576Z.
- [44] Singh, S. R.; Singh, G. Lattice-imaging studies on intergrowth structures of silicon carbide. Acta Crystallogr. A36(5): 779-784; 1980. CA 93:16159331A.
- [45] Guo, Chang-Lin. Crystal structure of silicon carbide polytype 147R(b). K'o Hsueh T'ung Pao. 24(23): 1080-1083; 1979. CA 92:10086296K.
- [46] Lange, F. F. Eutectic studies in the system Si3N4-Si2N2O-Mg2SiO4. J. Am. Ceram. Soc. 62(11-12): 617-620: 1979.
- D. Preparation
- [1] Ando, Yoshinori; Uyeda, Ryozi. Preparation of ultrafine SiC particles by gas evaporation. J. Am. Ceram. Soc., Comm. 64(1): C12-C13; 1981.
- [2] Suzuki, Hiroshige; Hase, Teizo. Boron transport and change of lattice parameter during sintering of b-SiC. J. Am. Ceram. Soc. 63(5-6): 349-350; 1980. CA 93:12119065K.
- [3] Sekercioglu, I.; Wills, R. R. Effect of Si3N4 powder reactivity on the preparation of the Si2N2O-Al2O3 silicon aluminum oxynitride solid solution. J. Am. Ceram. Soc. 62(11-12): 590-593; 1979.
- [4] Guha, J. P.; Goursat, P.; Billy, M. Hot-pressing and oxidation behavior of silicon nitride with ceria additive. J. Am. Ceram. Soc. 63(1-2): 119-120; 1980.
- [5] Loehman, Ronald E.; Rowcliffe, David J. Sintering of Si3N4-Y2O3-A12O3. J. Am. Ceram. Soc. 63(3-4): 144-148; 1980.
- [6] Rahaman, M. N.; Riley, F. L.; Brook, R. J. Mechanisms of densification during reaction hot-pressing in the system Si-Al-O-N. J. Am. Ceram. Soc. 63(11-12): 648-653; 1980.
- [7] Wills, R. R.; Sekercioglu, I.; Niesz, D. E. The interaction of molten silicon with silicon aluminum oxynitrides. J. Am. Ceram. Soc. 63(7-8): 401-403; 1980.



- [8] Galasso, F. S.; Veltri, R. D. Sintering of Si3N4-Y2O3 under nitrogen pressure. J. Am. Ceram. Soc., Comm. 64(1): C15-C16; 1981.
- [9] Greskovich, C.; Prochazka, S. Stability of Si3N4 and liquid phase(s) during sintering. J. Am. Ceram. Soc., Comm. 64(7): C96-C97; 1981.
- [10] Yajima, S.; Hasegawa, Y.; Hayashi, J.; Iimura, M. Synthesis of continuous silicon carbide fiber with high tensile strength and high Young's modulus. Part 1. Synthesis of polycarbosilane as precursor. J. Mater. Sci. 13(12): 2569-2576; 1978. CA 90:10072495W.
- [11] Bind, Jean Marie. Phase transformation during hot-pressing of cubic silicon carbide. Mater. Res. Bull. 13(2): 91-96; 1978. CA 88:22161820Z.
- [12] Ruska, J.; Gauckler, L. J.; Petzow, G. Phase transformation of cubic silicon carbide during hot-pressing with aluminum and aluminum oxide additions. Sci. Ceram. 9: 332-338; 1977. CA 90:08059848U.
- [13] Enomoto, Ryo; Tanaka, Hiroyuki. Oxidation resistant silicon carbide refractories. Japan. Kokai. Patent No.: 78 64213. Applic. No.: 76/139719. Date: 11/19/76. CA 89:22184650D.
- [14] Tomibe, Tadayoshi; Kamiko, Michiharu; Kimoto, Gohei; Ohnuki, Hideo. Oxidation-resistant silicon carbide heating elements. Jpn. Kokai Tokkyo Koho. Patent No.: 79 64512. Applic. No.: 77/130868. Date: 11/2/77. CA 91:24195059K.
- [15] Yanagi, Hiroki. Prevention of oxidation for graphite or silicon carbide refractories. Jpn. Kokai Tokkyo Koho. Patent No.: 79 47712. Applic. No.: 77/114933. Date: 9/24/77. CA 91:18144964U.
- [16] Enomoto, Ryo; Tanaka, Hiroyuki; Hara, Kazuhisa. Silicon carbide-based oxidation-resistance coating for refractories. Jpn. Kokai Tokkyo Koho. Patent No.: 79 43911. Applic. No.: 77/111073. Date: 9/14/77. CA 91:18144960Q.
- [17] Inomata, Kichizo; Tanaka, Hidehiko. Silicon carbide sintered body with high strength and oxidation resistance. Jpn. Kokai Tokkyo Koho. Patent No.: 80 20269. Applic. No.: 78/93328. Date: 7/31/78. CA 93:08078282H.




- [18] Taguchi, Akira. Recrystallization-type silicon carbide refractory material with improved oxidation resistance.

 Jpn. Kokai Tokkyo Koho. Patent No.: 79 95614. Applic.
 No.: 78/1699. Date: 1/11/78. CA 92:04027361E.
- [19] Seiter, H. Preparation and doping of epitaxial layers of silicon carbide. Report. BMFT-FB-T-79-125; Order No. 81-10878; 1979; 44 pp. CA 94:22183552Q.

E. Properties

- [1] Ziegler, G.; Bentsen, L. D.; Hasselman, D. P. H. Orientation effects on the thermal diffusivity of hot-pressed silicon nitride. J. Am. Ceram. Soc., Comm. 64(2): C35-C36; 1981.
- [2] Ehlert, Thomas C. Thermal decomposition of the oxynitrides of germanium and the heat capacity of the oxynitrides of silicon and germanium. J. Am. Ceram. Soc., Comm. 64(2): C25-C26; 1981. Correction. 64(8): C114; 1981.
- [3] Moon, Kenneth A.; Kant, Arthur; Croft, William J., Heats and free energies of formation of two sialons by mass spectrometry. J. Am. Ceram. Soc. 63(11-12): 698-702; 1980. Correction. 64(2): 124; 1981.
- [4] Leedecke, C. J. Electrical properties of some Y-Si-Al oxymitride glass-ceramics. J. Am. Ceram. Soc. 63(7-8): 479-480; 1980.
- [5] Wright, R. B.; Varma, R.; Gruen, D. M. Raman scattering and SEM studies of graphite and silicon carbide surfaces bombarded with energetic protons, deuterons and helium ions. J. Nucl. Mater. 63: 415-421; 1976.
- [6] Gruber, P. E. Mechanical properties of silicon carbide filaments. Proc. Int. Conf. Mech. Behav. Mater., 2nd. 1330-1334; 1976. CA 87:266203761T.
- [7] Singh, T. N.; Roy, B. N. Lattice dynamics of beta-silicon carbide. Nuovo Cimento Soc. Ital. Fis. B. 41B(1): 198-204; 1977. CA 87:22175852C.
- [8] Berry, T. Accurate measurement of lattice parameters using a Bragg-Brentano x-ray diffractometer applied to neutron irradiated silicon carbide. North. Div. Rep ND-R - U. K. At. Energy Auth. ND-R-143(D). Risley/Warrington, Engl.; 1979; 20 pp. CA 91:12100270K.
- [9] Glagovskii, A. A.; Ivanov, S. N.; Makletsov., A. N. Absorption of ultrasonic waves by silicon carbide. Fiz. Tverd. Tela, Leningrad. 19(11): 3467-3468; 1977. CA 88:08055173F.



- [10] Lyubimskii, V. M. Elastic constants of silicon carbide polytypes. Fiz. Tverd. Tela, Leningrad. 18(10): 3111-3112; 1976. CA 86:08049304S.
- [11] Leedecke, C. J.; Loehman, Ronald E. Electrical properties of yttrium-aluminum-silicon oxynitride glasses. J. Am. Ceram. Soc. 63(3-4): 190-193; 1980.
- [12] Fegley, M. Bruce, Jr. The thermodynamic properties of silicon oxynitride. J. Am. Ceram. Soc., Comm. 64(9): C124-C126; 1981.

F. Reaction Products

- [1] EerNisse, E. P. Stress in thermal SiO2 during growth. Appl. Phys. Lett. 35(1): 8-10; 1979.
- [2] Lora-Tamayo, A.; Dominguez, E.; Lora-Tamayo, E.; Llabres, J. A new model of the thermal growth of a silicon dioxide layer. Appl. Phys. 17: 79-84; 1978.
- [3] Heubner, K. Structure and properties of silicon dioxide and silicon oxide (SiOx). Phys. Halbleiteroberflaeche. 11: 1-12; 1980. CA 94:18148780R.
- [4] Varshal, B. G.; Shvorneva, L. I.; Danishevskaya, E. D.; Pavlova, G. A. Thermal expansion of the cristobalite-like 0.06 titanium dioxide-0.94 silicon dioxide solid solution. Izv. Akad. Nauk SSSR, Neorg. Mater. 17(1): 180-182; 1981. CA 94:14112754W.



NBS-5.2.10(D) - MICROSTRUCTURE AND FRACTURE IN REACTIVE ENVIRONMENTS

RESULTS FROM PRIOR QUARTERS

An apparatus for mechanical testing structural ceramics in gaseous combustion products at temperatures up to 1400 °C has been designed, and the components required to construct the apparatus have been ordered from commercial suppliers. The apparatus includes a laboratory box furnace which is gas tight, a gas blending system which can control the flow and composition of a mixture of 5 gases (SO $_2$, H $_2$ O, CO $_2$, O $_2$, and N $_2$), and an existing, displacement rate controlled, loading machine. The furnace will provide a 6 inch cube cavity that is heated electrically by molybdenum disilicide elements. The gas mixture at nominally one atmosphere pressure will flow through the furnace cavity. The gas blending system controls the flow of each gas component by the thermal conductivity of its mass.

DISCUSSION OF CURRENT ACTIVITIES

The furnace system is under construction by its manufacturer. We have conferred with the manufacturer to have the furnace modified so that load bearing rods can be introduced through top and bottom ports of the furnace. Regular access to the furnace cavity for placement of a test specimen between the bearing rods is made through a sealed, water-cooled front door.

Gas tight fixtures were designed for attachment to the top and bottom furnace posts so that loading could be transferred from the test machine to a specimen in the furnace. Commercial flanges and bellows required for the fixtures were obtained. Accessory components are presently being machined to hold the bearing rods. All of these parts will then be welded together to make the fixtures.

The commercial gas blending system was delivered. The system includes separate controllers which maintain the flow of each gas individually over a specified flow range before blending. Unfortunately, the supplier inadvertently transposed the ranges requested for $\rm SO_2$ and $\rm N_2$. The units for these two gases were returned for recalibration.

PROPERTY AND ADDRESS OF PERSONS OF PERSONS ASSESSED.

SECURE OF THE PARTY OF THE PARTY OF

consisted process of contraction of the tenth of the last contract, and the composition process of contract of the separate of the tenth of the tenth of the tenth of the contract of the cont

DESCRIPTION OF PERSONS PARTY AND PERSONS PROPERTY.

CAS SIGN PLANTED AND ADDRESS OF THE PROPERTY OF THE PARTITION OF THE PARTY OF THE P

The related out of the real has been partially upon the country of the country of

Alteration of the laboratory room facilities were initiated to provide power and cooling-water to the furnace and to exhaust the flow of gas from the furnace out of the room.

Although construction of the apparatus is not yet completed, we expect that its assembly will soon be underway and its operation will be verified on schedule by December 1981.

DS:

Altered of the second of the second and to the second of t

The conference and how quantities of the anticompanies of the conference will be proported and the description will be proported and the description of the conference and the conferenc